

Invitation for Bid No. 2021-076

880 Zone & 935 Zone Interconnections with Charlotte Water

ADDENDUM No. 3

ISSUE DATE: June 8, 2021

Responding Offerors on this project are hereby notified that this Addendum shall be made a part of the above named IFB document.

The following items add to, modify, and/or clarify the IFB documents and shall have the full force and effect of the original Documents. This Addendum shall be acknowledged by the Offeror in the IFB document.

Union County, NC
880 Zone & 935 Zone Interconnections with Charlotte Water
Project Number: WT109

ADDENDUM #3

ISSUED DATE: June 8, 2021

RE-BID DATE: June 15, 2021, 10:00 AM

TO ALL BIDDERS:

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents and all previous Addenda.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

Below are changes, additions, and/or clarifications to the bid documents for this project.

Q/A & Clarifications

Item 1: Question: Note 2 on sheet C-02 and C-03 states the below:

“See sheet C-04 for Charlotte Water standard detail “12-inch FMCT water meter and precast concrete vault service connection. Furnish and install all components as shown in the detail unless otherwise called for in the plans.”

The 12-inch FMCT detail shows components that are not shown on the octave meter vault detail such as a 2” bypass line with 2” meter and a 12” check valve. Will these be required to be installed?


Answer: Yes, items shown inside the vault in Charlotte-Mecklenburg Utilities - Detail Q on Sheet C-04 of the construction plans are required to be installed, including a 2” bypass line with 2” meter and 12” check valve, among other items. There are items outside the vault that are not required and are not shown on Sheets C-02 and C-03 of the plans to be installed, including Item No. 1 – 12” Tapping Sleeve & Valve; Item No. 4 – 12” Adapter/12” Gate Valve; Item No. 18 – 2” Temporary Blow Off; Item No. 23 – Minimum of Three Concrete Brick Courses Under Access Door Frame.

Addendum #3, IFB #2021-076, 880 Zone & 935 Zone Interconnections with Charlotte Water

This addendum and all associated specifications sections and revised Contract Documents will be uploaded to the online plan room and distributed to registered plan holders via email.

Receipt of this addendum must be acknowledged on Page 1 of EJCDC C-410 – Bid Form.

Sincerely,



Michael S. Caldwell, P.E.
Project Manager
Union County Government

.....

END OF ADDENDUM #3