



Invitation for Bid No. 2022-033

Eastside Pump Station Interior Painting

.....

ADDENDUM No. 1

ISSUE DATE: February 28, 2022

Responding Bidders on this project are hereby notified that this Addendum shall be made a part of the above named IFB document.

The following items add to, modify, and/or clarify the IFB documents and shall have the full force and effect of the original Documents. This Addendum shall be acknowledged by the Offeror in the IFB document.

A) Add/Delete

1. **Add:** In Section 6.1, Specifications, pg. 8, the information listed below. The information listed below is being added to this section and other applicable areas within this IFB document.

Top Floor Above Grade CMU Walls:

Surface Prep: Prepare to a clean, dry and dull surface

Top Coat: Sherwin Williams Pro Industrial Waste Based Epoxy @ 4-6 mils DFT

Bottom Floors - Walls and Ceilings:

Surface Prep: SSPC SP13

1st Coat: Sherwin Williams Loxon XP @ 85-110 s/f per gallon

2nd Coat: Sherwin Williams Loxon XP @ 85-110 s/f per gallon

B) Questions & Answers

1. **Question:** What is the estimated construction budget for this project?

Answer: Not available at this time.

2. **Question:** Please confirm the existing HVAC system will maintain an ambient heated or conditioned temperature of approximately 70-72 degrees Fahrenheit during paint installation by the subcontractor.

Answer: The HVAC system is being repaired and will be in service prior to work beginning. If additional heat is required in the building, Union County Water will provide space heaters.

3. **Question:** Please confirm bidders are allowed to use onsite non-potable water supply and 120-volt electricity during installation effort at no additional costs.

Answer: The awarded vendor will be allowed to use these services at no additional cost.

4. **Question:** Please confirm all 3rd party testing (if applicable) is by Others and not included under this scope of supply.

Answer: Testing will be performed by a third party.

END OF ADDENDUM No.1